



BROWARD COUNTY

BOARD OF RULES & APPEALS

One North University Drive, Suite 3500-B
Plantation, Florida 33324
Phone (954) 765-4500 Fax: (954) 765-4504
www.broward.org/codeappeals

2010 FBC FORMAL INTERPRETATION

2012 Voting Members

Mr. Abbas H. Zackria, CSI
Chair
Mr. Ron Burr
Vice-Chair
Mr. John Famularo,
Roofing Contractor
Mrs. Shalanda Giles Nelson,
General Contractor
Mr. Gary Elzweig, P.E
Structural Engineer
Mr. Richard Smith,
Master Plumber
Mr. Jeffrey Lucas
Fire Service Professional
Mr. Allan Kozich, P.E.
Electrical Engineer
Mr. Gregg D'Attile,
Mechanical Contractor
Mr. John R. Smith,
Representative Disabled
Community
Mr. John Sims,
Master Electrician
Mr. Jay Shechter,
Consumer Advocate
Mr. Henry Zibman, P.E.
Mechanical Engineer

2012 Alternate Board Members

Mr. Steven Feller, P.E.
Mechanical Engineer
Mr. Alberto Fernandez,
General Contractor
Mr. Daniel Lavrich, P.E.
Structural Engineer
Assistant Chief Jeff Moral, CFO
Fire Service
Mr. David Rice, P.E.
Electrical Engineer
TBA
Master Plumber
Mr. David Tringo,
Master Electrician
Mr. William Flett,
Roofing Contractor
Mr. Donald Zimmer, AIA
Architect

Board Attorney
Russell White, Esq.

Board Administrative Director
James DiPietro

—ESTABLISHED 1971—

TO: All Building Officials
FROM: James DiPietro, Administrative Director
DATE: July 11, 2008 / **Revised September 11, 2008 RE-ISSUED: MARCH 1, 2009**
RE-ISSUED: MARCH 15, 2012
SUBJ: **FL Mechanical Code, 602.2.1, Materials Exposed Within Plenums**

This portion of the Interpretation concerns the residential portion of R-2 occupancies.

At its meeting of July 10, 2008 the Broward County Board of Rules and Appeals approved the following Formal Interpretation.

Section 602.2.1 of the Florida Mechanical Code requires materials exposed within plenums to be noncombustible or shall have a flame spread index of not more than 25 and a smoke-developed index of not more than 50 when tested in accordance with ASTM E 84 (2001 Edition).

CPVC Flowguard Gold Pipe, SDR11 was tested by Southwest Research Institute using a *modified* ASTM E-84 test methodology in the following sizes.

.5 inch (nominal) water filled CPVC pipe: SwRI Project No. 01.04017.01.301b [1]

2 inch (nominal) water filled CPVC Pipe: SwRI Project No. 01.04017.01.301c [1]

.5 inch (nominal) empty CPVC Pipe: SwRI Project No. 01.10083.01.158e

.75 inch (nominal) empty CPVC Pipe: SwRI Project No. 01.10083.01.158f [1]

All four Modified ASTM E-84 Tests showed flame spread indices of not more than 25 and smoke-developed indices of not more than 50.

By accepting these four Modified ASTM-E 84 Tests, the Broward County Board of Rules and Appeals approved the use of CPVC Flowguard Gold Pipe, SDR11 installed in Mechanical Closets and Mechanical Equipment/Appliance Rooms used as plenums in the residential portion of R-2 Occupancies. Approval is limited to .5 inch (nominal) thru 2 inch (nominal) water filled CPVC and .5 inch (nominal) and .75 inch (nominal) empty CPVC pipe.

At its meeting of September 11, 2008 the above Interpretation was expanded to include the following language which applies to both commercial and residential occupancies:

CPVC piping may be accepted for use in plenums in instances where the manufacturers have tested their product with an approved testing agency to an acceptable alternate method to ASTM E-84 – “Standard Test Method for Surface Burning Characteristics of Building Materials”. Evidence must be submitted to the Authority Having Jurisdiction (AHJ) that the piping has a flame spread index of not more than 25 and a smoke developed index of not more than 50 when tested in general accordance with ASTM E-84, 2001 Edition, Pipe can be tested empty or water filled and in various pipe diameters.

EFFECTIVE DATE: OCTOBER 20, 2005

RE-ISSUED: MARCH 1, 2009

RE-ISSUED: MARCH 15, 2012

*******PLEASE POST AT YOUR PERMIT COUNTER*******